



COMMONWEALTH OF VIRGINIA
COUNTY OF HENRICO

The complete Addendum 1 will be mailed to plan holders.

DEPARTMENT OF GENERAL SERVICES
PAUL N. PROTO
DIRECTOR

ADDENDUM NO. 1

To: Prospective Bidders and Others Concerned
From: County of Henrico/Draper Aden Associates
Date: August 11, 2010
Re: Hermitage Farms Water System Improvements
DAA #R09296R, County Project No. 00812
Bid Request No. 10-8883-6CE

The following changes, corrections, deletions, clarifications, and/or additions constitute Addendum No. 1 to the project and are made to the Project Manual based on regulatory issues and questions received from potential bidders. All other general terms, conditions, specifications, and drawings shall remain the same. **Please acknowledge receipt of this Addendum No. 1, dated August 11, 2010 in the space provided on the Bid Form. Failure to acknowledge this addendum may result in your bid being declared non-responsive.**

Additional changes, corrections, deletions, clarifications, and/or additions:

1. Plumbing permits will be required for all work on private property, including turning of water services under houses. The contractor will be responsible for acquiring these permits. Refer to Section 01000/1.02.G of the Project Manual.
2. All new water services shall be 1-inch copper. All materials necessary to provide new water services as shown on the plans shall be included in the contractor's bid price.
3. Per Department of Public Works (DPW) Note #6 on Sheet 2 of the plans, temporary or permanent asphalt shall be installed in all roadway trenches located in the County right-of-way before the end of each workday.
4. Stone backfill shall be provided for water mains in roadway shoulders in accordance with Department of Public Works (DPW) Note #27 on Sheet 2 of the plans, and the "Backfill for Pressure Pipe Trench in Roadway Shoulder" detail on Sheet 20.
5. The work along Staples Mill Road, shown on Sheet 15 of the plans, will require a VDOT permit, which will be acquired by the Henrico County Department of Public Utilities. The work hours within the VDOT right-of-way will be specified on the permit. A copy of the VDOT permit is included with this addendum.

6. The intent of the work along Staples Mill Road, shown on Sheet 15, is not to impact the travel lanes of Staples Mill Road; however, if one or more travel lanes of Staples Mill Road will be impacted as a result of the work to be performed, the contractor shall provide a traffic control plan in accordance with the VDOT permit, at no additional cost to the owner.
7. On the Water and Sewer Crossing detail on Sheets 11 and 12 of the plans, remove the word “Temporary.” The note should read “The contractor shall provide structural support under the existing sewer to prevent settling of joints during installation of the new water main.”
8. Pavement overlay shall be performed in accordance with the symbols shown on the revised legend, which is included with this addendum.
9. Existing sewer laterals are either 4-inch or 6-inch diameter pipe, and shall be replaced with 6-inch pipe from the main to the site inspection port (S.I.P.) and, if the existing lateral is 4-inch, shall be transitioned to 4-inch pipe on the customer side of the S.I.P.

COUNTY OF HENRICO, VIRGINIA
GENERAL SERVICES/PURCHASING
CAROLYN L. EFFORD, CPPB
(804) 501-5688
eff@co.henrico.va.us